

## RELAY TEST SET/ SECONDARY CURRENT INJECTION



Relay Test Set 0-100Amp@ 600Va  
Capacity as per customer requirement  
**Input**-230vac (Single Phase)  $\pm$  10%  
**Output**-0-100Amp.  
**Duty**-15min on/15 min off  
**Control**-manual.  
**Output**-Terminal type.

### Protection-

1. Fuse input side

### Indication:

LT on, Output on/off.

### Push button:

Output ON/OFF.

### Meter type :

AC Volt meter, DC Volt meter, Amp meter.  
(size 48/96 digital type).

**Timer digital type** :- 9999  $\mu$  sec. to milli sec.  
(48/96)

**Resolution** : 0.1 (Digital)

### Accessories;

Input lead 3meters.  
Output lead 1.5meters.  
Measurement lead 3meters.  
Earthing lead with clip 3meters.

### Size of set.

Panel (460mm/300mm/200mm) $\pm$ 10%.